BRUHAT BENGALURU MAHANAGARA PALIKE

YELAHANKA ZONE

NAME OF WORK : PROVIDING CEMENT CONCRETE ROADS TO INSPECTOR RAMAIAH ROAD AND SURABHI LAYOUT AT WARD NO.01

						Estimate Cost Rs.	50.00	Lakhs
Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
Removing **B.S. slab** of Drain and stacking.(P No.25 / I N 5.32)								
Surabhi Layout	Sqm							
Cross Road		1	150.00	0.90		135.00		
						135.00	65.72	**8872.20**
Basic Rate	62.00							
Area Weightage @ 6%	3.72							
Total	**65.72**							
KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)								
Surabhi Layout (desilting)	Cum							
Cross Road		1	150.00	0.60	0.60	54.00		
						54.00	86.92	**4693.68**
Basic Rate	82.00							
Area Weightage @ 6%	4.92							
Total	**86.92**							
3 **Refixing stone slabs** of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)							-	
	Sqm							
			80% of Qty Vide Item No.1			**108.00**	80.56	**8700.48**
Basic Rate	76.00							
Area Weightage @ 6%	4.56							
Total	**80.56**							
4 KSRB 2-2.1 : **Earth work excavation** for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)								
Surabhi Layout	Cum							
for New RCC Drain		1	140.00	1.00	1.10	154.00		
						154.00	200.34	**30852.36**
Basic Rate	189.00							
Area Weightage @ 6%	11.34							

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
Total	200.34							
KSRB 2-1.1 : Earthwork in surface excavation in **ordinary soil** for **levelling and lowering** the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)								
for Road	Cum							
Surabhi Layout		1	120.00	5.00	0.40	240.00		
		1	36.00	4.00	0.35	50.40		
		1	150.00	5.00	0.30	225.00		
Cross Roads of Ayyappa temple Road		3	20.00	4.00	0.30	72.00		
						587.40	166.42	**97755.11**
Basic Rate	157.00							
Area Weightage @ 6%	9.42							
Total	**166.42**							
KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)								
	Cum							
			Qty Vide Item No.2+4+5			**795.40**	100.00	**79540.00**
Average Weight of Earth 1.28 Tonne/Km								
Basic Rate Lead Charges for 10.00 Kms (2.50X1.28X10.00)	32.00							
Addl loading and unloading Item No 17.1)	68.00						-	
Total	**100.00**	85.65						
KSRRB M400-6.1. Construction of granular sub-base by providing close graded material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material (P.No.155 It.No.20.4.2)								
for Road	Cum							
Surabhi Layout		1	120.00	5.00	0.15	90.00		
		1	36.00	4.00	0.15	21.60		
		1	150.00	5.00	0.15	112.50		
Cross Roads of Ayyappa temple Road		3	20.00	4.00	0.15	36.00		
						260.10	1665.26	**433134.13**
Basic Rate	1571.00							
Area Weightage @ 6%	94.26							
Total	**1665.26**							

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)								
for Road	Cum							
Surabhi Layout		1	140.00	1.00	0.15	21.00		
		1	120.00	5.00	0.15	90.00		
		1	36.00	4.00	0.15	21.60		
		1	150.00	5.00	0.15	112.50		
Cross Roads of Ayyappa temple Road		3	20.00	4.00	0.15	36.00		
						281.10	5159.02	**1450200.52**
Basic Rate	4867.00							
Area Weightage @ 6%	292.02							
Total	**5159.02**							
KSRB 4.9.2:Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3-do-TMT Bars Fe 500 P.17/It.No.4.46.2 (rates effects from 01-07-2017)								
	tonne	No.of Bars	Vidth/Lengt	Rmtr	Kg/Rmtr	Total in Kg		
10mm dia main bar spacing at 200mm c/c	2	700	2.40	3360.00	0.617	2073.12		
8mm dia dist bar spacing at 200mm c/c	2	12	140.00	3360.00	0.395	1327.20		
					in Kg	3400.32	-	
					in Qtl	34.0032		
					in tonne	**3.4003**	64243.42	**218448.19**
Basic Rate	60607.00							
Area Weightage @ 6%	3636.42							
Total	**64243.42**							
KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.21 (P.15 / I.4.31)								
	Sqm							
		2x2	140.00		0.90	504.00		
						504.00	310.58	**156532.32**
Basic Rate	293.00							
Area Weightage @ 6%	17.58							
Total	**310.58**							

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
Providing & laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs , with 20mm and down size graded granite metal,coarseaggregated @ 0.69cum ,and fine aggregated @ 0.460cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed -2008 machine mixed concrete laid in layers not exceeding 15 crns thick, vibrated for all works in foundation for footings,pedestals,retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts,struts, buttresses, bed blocks, anchor blocks, plinths etc.,including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.specifications No.KBS 4.1,4.6 (P.No.13/ I.No:4.11)								
	Cum							
bed		1	140.00	1.00	0.15	21.00		
Side wall		2	140.00	0.15	0.90	37.80		
						58.80	6371.66	**374653.61**
Basic Rate	6011.00							
Area Weightage @ 6%	360.66							
Total	**6371.66**							
Providing and fixing **RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm** and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete								
	Sqm							
for New Rcc Drain		1	140.00	0.90		126.00		
		80% of Qty Vide Item No.1				27.00		
	Sqm					**153.00**	2100.00	**321300.00**
Data Rate	**2100.00**							
Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete **(RMC)** M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.) Page No.18 / Item No. 4.48)							-	
for Road	~~Sqm~~ Cum							
Surabhi Layout		1	120.00	5.00	0.15	90.00		
		1	36.00	4.00	0.15	21.60		
		1	150.00	5.00	0.15	112.50		
Cross Roads of Ayyappa temple Road		3	20.00	4.00	0.15	36.00		
	Cum					**260.10**	6231.74	**1620875.57**
Basic Rate	5879.00							
Area Weightage @ 6%	352.74							
Total	**6231.74**							
Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift (P.177/ I.22.7)								

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
for Road	Sqm							
Surabhi Layout		1	120.00	5.00		600.00		
		1	36.00	4.00		144.00		
		1	150.00	5.00		750.00		
Cross Roads of Ayyappa temple		3	20.00	4.00		240.00		
						1734.00	95.40	**165423.60**
Basic Rate	90.00							
Area Weightage @ 6%	5.40							
Total	**95.40**							
Providing Groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine generator and HOM of machinery including cost of blade, coolant etc., including cleaning aof groove & providing sand and hot bitumen fillars and filler metal etc.,including cost of conveyance of all materials, labour,lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification. (P.178/ I.22.8)								
for road	m							
		20	5.00			100.00		
		6	4.00			24.00		
		18	5.00			90.00		
						214.00	121.90	**26086.60**
Basic Rate	115.00							
Area Weightage @ 6%	6.90							
Total	**121.90**							
Miscellaneous and unforeseen charges	LS							**2932.00**
						Grand Total Amount	-	**5000000.00**

(Rupees Fifty Lakhs Only)

RTIFICATE

The site has been inspected and the work is found to be necessary.
The rates adopted are as per PW,P IWTD SR of 2016-17 and data rate of Bangalore Circle.
The provisions were made in this estimate are necessary and adequate.
The area comes under the Bruhat Bengaluru Mahanagara Palike Limits.

Assistant Engineer
Ward No.01

Assistant Executive Engineer
Yelahanka Sub-Division
B.B.M.P

Executive Engineer
Yelahanka Division
B.B.M.P

Administrative Approval
Accorded For Rs.50.00 lakhs
Head of A/C...P-1878
CER NO :...55/17-18 Dt.: 09/10/2017
E.E. (Project)

Technical Sanction
Accorded For Rs.50.00 lakhs
Head of A/C...P-1878
CER NO :...240..... Dt.: 10/10/17
TA CE (YNK)